



MAR 30 2021

MS. KATRINA NOKLEBY
MLA, GREAT SLAVE

Oral Question 515-19(2) Highway Infrastructure Projects in the Next Year

This letter is in follow-up to the Oral Question you raised on February 8, 2021 regarding highway infrastructure projects in the next year. I committed to providing a list of highway projects planned for next year, from April 1, 2021 to March 31, 2022, which is attached for your information.

Sincerely,

Diane Archie
Minister, Infrastructure

Attachment

c. Clerk of the Legislative Assembly

Legislative Coordinator
Executive and Indigenous Affairs

2021/22 HIGHWAY IMPROVEMENT AND STRATEGIC INFRASTRUCTURE PROJECTS

2021/22 Highway Improvement Projects (Capital)					
Highway/Road	Description	Current Phase	Kilometre (s)	Construction Start date (estimated)	Construction End date (estimated)
Highway 1	Rehabilitation including embankment widening, culvert replacement and chipseal	Design & Canada Treasury Board approval	222 to 234	June 2021	September 2023
Highway 3	Highway rehabilitation including ROW clearing, leveling, culvert replacement, chipseal and line painting at selected sections	Negotiation	240 to 244	May 2021	September 2021
	Surface repairs/resurfacing and chipsealing	Design	0 to 23	June 2021	August 2022
	Produce and stockpile material	Construction	188, hwy. 1	May 2021	July 2021
	Chipseal overlay/repair	Construction	164 to 332	June 2021	August 2021
	Hwy 3 -Asphalt Repair	Design	336.86 to 337.66	June 2021	July 2021
Highway 4	Highway repairs and rehabilitation including repairing dips, embankment widening, culvert replacement and chipseal	Construction	54.6 to 60	May 2021	September 2023
Highway 6	Chipseal overlay	Construction	70 to 90	May 2021	September 2021
Highway 7	Rehabilitation work including embankment widening and culvert replacement.	Permitting & Canada Treasury Board approval	20 to 38	June 2021	September 2023
Highway 8	Culvert replacement	Design	147 and 266.1	July 2021	March 2022
	Rehabilitation work including embankment widening, culvert replacement and bush/tree clearing	Construction	146.6 to 150	July 2021	October 2021
	Highway widening	Construction	269.3 to 272.5	June 2021	August 2021
	Marine bypass upgrade	Construction	269.3 to 272.5	June 2021	August 2021
Highway 9 - Tłıchǫ Highway	Construction of an all-season road approximately 97 km in length with a 60 m right-of-way.	Construction	From Highway 3 to Whati	September 2019	November 2022
Highway 10 - Inuvik Tuktoyaktuk Highway	One of two planned pull-outs to provide enhanced access to road users (funding will come from Dept. ITI)	Construction	Unknown at this time. Community consultations under way. April / May 2021	June 2021	August 2021
	Road resurfacing with 5,000 cubic meters of materials, the application of calcium chloride, and other Associated Engineering recommended	Construction	Various	June 2021	August 2021

	improvements if budget is available.				
	Crushing of 18,000 cubic meters of aggregate, pending available funding, to be used on future and ongoing Highway operations and maintenance.	Construction	Pit 312	June 2021	August 2021
	Continue construction of concrete arch bridge-culvert at Gunghi Creek	Construction	131.2	December 2020	August 2021
Mackenzie Valley Winter Road Bridges	Oscar Creek Bridge – move the existing bridge onto the Mackenzie Valley Highway alignment	Design and Project Permitting	1054 (Mackenzie Valley Winter Road)	February 2022	2022
Bridge/Culverts Rehabilitation and Replacements	Various bridges and culvert projects	Pre-engineering and Design	Various	Ongoing	Ongoing
Dettah Access Road	Chipseal overlay	Construction	6-12	July 2021	August 2021
Rae Access Road	Upgrades including new gravel surface and chipseal overlay	Construction	0-10	July 2020	October 2021
2021/22 Strategic Infrastructure Projects (New Assets)					
Highway/Road	Description	Current Phase	Kilometre (s)	Construction Start date (estimated)	Construction End date (estimated)
Highway 1	Prohibition Creek Access Road	Final Design	13 km	Winter 2022	2024
	Mount Gaudet Access Road	Permitting	15 km	Winter 2022	2024
Deh K'e Frank Channel Bridge	Replacement	Planning – Pending Funding	243.8	TBD	TBD
Great Bear River Bridge	Construction of a new two-lane bridge measuring 460 meters in length over the Great Bear River near the community of Tulita	Design	938 (Mackenzie Valley Winter Road)	Fall 2022	2026